

Order List

Deck Name: Custom

Lumber

QUANTITY	MATERIAL
2	2 x 10 x 8'
9	2 x 10 x 10'
8	2 x 10 x 14'
14	2 x 10 x 16'
1	2 x 10 x 12'
12	6 x 6 x 8'
6	5/4 x 6 x 14'
43	5/4 x 6 x 16'
2	5/4 x 6 x 8'
4	5/4 x 6 x 10'
19	5/4 x 6 x 12'
1	4 x 4 x 8'
6	4 x 4 x 12'
4	2 x 4 x 8'
2	2 x 4 x 14'
3	2 x 4 x 12'
4	2 x 4 x 16'
152	2 x 2 x 36"
5	2 x 12 x 14'
1	2 x 6 x 8'

Hardware

QUANTITY	DESCRIPTION
34	Standard Joist Hanger
11 lbs	10d nails x 3"
2	Left Skewed Joist Hanger
4 lbs	16d nails x 3.5"
2 lbs	10d nails x 1.5"

QUANTITY	DESCRIPTION
2	Right Skewed Joist Hanger
8	Post To Beam Connector
12	Post Base Connector
12	5/8 x 4 inch wedge anchor bolt
2	14 inch x 30 foot vinyl roll flashing
4	8 foot section Z flashing
56	3.5 inch structural screw
2	Concealed Joist Hanger
8	1/2 x 8 inch bolt w/ washer
19	Hurricane Tie
5 lbs	2.5 inch screw
33 lbs	3 inch screw
19	6 inch structural screw
5	Stair Stringer Connector
124	60 lb bags of concrete